

# Cost Comparisons



70mm Clay Bricks on Timber Frame									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	Brick Supplied	Mortar	Ties	Labour	TOTAL
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 51.00	\$ 8.00	\$ 2.60	\$ 55.00	\$ 212.60
40mm Polystyrene with Texture Coating on Timber Frame									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	EIFS System				TOTAL
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 130.00				\$ 226.00
90mm Clay Bricks on Timber Frame									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	Brick Supplied	Mortar	Ties	Labour	TOTAL
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 61.00	\$ 8.00	\$ 3.00	\$ 60.00	\$ 228.00
75mm Hebel Powerpanel on Timber Frame									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	Powerpanel & Battens	Installation (Single storey)	Acrylic Coating		TOTAL
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 56.50	\$ 25.00	\$ 62.00		\$ 239.50
60mm Polystyrene with Texture Coating on Timber Frame									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	EIFS System	Acrylic Topcoat			TOTAL
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 135.00	\$ 14.00			\$ 245.00
190mm Polystyrene Block Concrete Filled									
Interior Paint	Gib, Fix & Stop	Laid Block	Reinforcing Steel	Concrete Fill	Plaster System				TOTAL
\$ 11.60	\$ 25.00	\$ 83.00	\$ 14.30	\$ 39.70	\$ 78.00				\$ 251.60
4.5mm Fibre Cement Sheeting & Solid Plaster on Timber Frame									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	H3 Timber battens installed	4.5mm Fibre cement installed	21mm Plaster	Paint	TOTAL
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 18.00	\$ 33.00	\$ 90.00	\$ 17.50	\$ 254.50
70mm Clay Bricks & Plaster on Timber Frame									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	Plasterbricks, mortar & ties supplied	Bricklaying Labour	15mm Plaster	Paint	TOTAL
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 46.10	\$ 48.15	\$ 55.00	\$ 17.50	\$ 262.75

Prices are based on national average rates from the Rawlinson NZ Construction Handbook 2005.  
 The rates exclude GST and any freight to remote areas.  
 The rates are for comparison purposes only and should not be used to form the basis of any quote.

# Cost Comparisons



<b>Hebel 200mm Thermoblock</b>									
Interior Paint	Gib, Fix & Stop	Hebel & Adhesive	Reinforcing & Grouting	Laying of Hebel	8mm Render & mesh	Render Labour	Paint		<b>TOTAL</b>
\$ 11.60	\$ 25.00	\$ 125.00	\$ 12.00	\$ 44.00	\$ 12.00	\$ 30.00	\$ 17.50		<b>\$ 277.10</b>
<b>Conventional 20 Series Masonry Strapped &amp; Lined</b>									
Interior Paint	Gib, Fix & Stop	50x50 Timber Strapping	50mm Insulation	Laid Block	Reinforcing Steel	Block Fill	12mm Plaster	Paint	<b>TOTAL</b>
\$ 11.60	\$ 25.00	\$ 25.00	\$ 15.62	\$ 99.00	\$ 14.30	\$ 36.70	\$ 38.20	\$ 17.50	<b>\$ 282.92</b>
<b>Hotbloc 20 Series Blocks with Insulating Plaster</b>									
Interior Paint	Gib, Fix & Stop	Laid Block	Reinforcing Steel	Block Fill	Insulated Plaster	Paint			<b>TOTAL</b>
\$ 11.60	\$ 25.00	\$ 118.00	\$ 14.30	\$ 23.00	\$ 93.00	\$ 17.50			<b>\$ 302.40</b>
<b>Strapped &amp; Lined 150mm Tilt Slab</b>									
Interior Paint	Gib, Fix & Stop	50x50 Timber Strapping	50mm Insulation	Tilt Slab installed	12mm Plaster	Paint			<b>TOTAL</b>
\$ 11.60	\$ 25.00	\$ 25.00	\$ 15.62	\$ 170.00	\$ 38.20	\$ 17.50			<b>\$ 302.92</b>
<b>150x25 Rusticated Cedar Weatherboards on Timber Frame</b>									
Interior Paint	Gib, Fix & Stop	Installed H1.2 Framing	Batts R2.2	Building Paper	Cedar Weatherboards	Oil Coating			<b>TOTAL</b>
\$ 11.60	\$ 25.00	\$ 42.00	\$ 10.70	\$ 6.70	\$ 198.00	\$ 12.75			<b>\$ 306.75</b>
<b>180mm Nirvana Insulated Tilt-panel</b>									
Interior Paint	Gib, Fix & Stop	Nirvana Panel Installed	12mm Plaster	Paint					<b>TOTAL</b>
\$ 11.60	\$ 25.00	\$ 255.00	\$ 38.20	\$ 17.50					<b>\$ 347.30</b>
<b>235mm Thermomass Insulated Tilt-panel</b>									
Interior Paint	Gib, Fix & Stop	Thermomass Installed	12mm Plaster	Paint					<b>TOTAL</b>
\$ 11.60	\$ 25.00	\$ 280.00	\$ 38.20	\$ 17.50					<b>\$ 372.30</b>

Prices are based on national average rates from the Rawlinson NZ Construction Handbook 2005.  
 The rates exclude GST and any freight to remote areas.  
 The rates are for comparison purposes only and should not be used to form the basis of any quote.